किरोड़ीमल कॉलेज

दिल्ली विश्वविद्यालय, दिल्ली-११०००७

KIRORI MAL COLLEGE

University of Delhi, Delhi-110007

NAAC Accredited A++ 3.54 CGPA, CYCLE 2 NIRF RANK 9

Date 22.09.2025

Sealed quotations are invited from the contractors of appropriate class registered with CPWD, M.E.S, Railways or working contractors of University of Delhi for the work "Exterior repair & painting at Principal's residence at Kirori Mal College , University of Delhi" so as to reach the college office by 4.00 p.m. on 07.10.2025.

S. No	Description of Items	Unit	Qty	Rate	Amount
1	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge.	cum	3		
2	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	sqm	350		
3	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	sqm	1350		
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sqm	250		
5	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	500		
6	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)	sqm	20		
				Total	

Conditions:

1. The work is to be completed in 45 days.
2. 1% water/electricity charges will be recovered.
3. CPWD Specifications will be followed rigidly.
4. Rates should be quoted both in words & figures.
5. Undersigned reserves the authority to reject any or all the quotations without assigning any reason thereof.

Principal

Email.: principal@kmc.du.ac.in दूरभाष:– 011-71219044