



किरोड़ीमल कॉलेज

दिल्ली विश्वविद्यालय, दिल्ली-११०००७

KIRORI MAL COLLEGE

University of Delhi, Delhi-110007
NAAC Accredited A++ 3.54 CGPA, CYCLE 2 NIRF RANK 9

Date: 30.06.2026

Sealed quotations are invited from the contractors of appropriate class registered with CPWD, M.E.S, Railways or working contractors of University of Delhi for the work "Repair of toilets, shower cabins, change rooms, baggage shelves and various other functional repairs at ground floor in the Sports complex building at Kirori Mal College, University of Delhi" so as to reach the college office by 4.00 p.m. on 10.13.07.2026.

S. No	Description of Items	Unit	Qty	Rate	Amount
1	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge	cum	5	494.1	2470.50
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level				
a	1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources: 3 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	0.2	8340.85	1668.17
b	1:4:8 (1 Cement: 4 coarse sand (zone-III) derived from natural sources: 8 graded stone aggregate 40 mm nominal size derived from natural sources)	cum	0.5	6812.00	3406.00
3	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement :4 coarse sand)	sqm	20	1123.8	22476.00
4	Extra for providing and placing in position 2 Nos 6 mm dia. M.S. bars at every third course of half brick masonry. sqm 104.80	sqm	20	104.8	2096.00
5	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand) or araldite, joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels. Granite stone slab of colour black, Cherry/Ruby red Area of slab over 0.50 sqm	sqm	19	5136.3	97589.70
6	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	sqm	22	1267.95	27894.90
7	Providing and fixing to existing door frames. 30 mm thick Fiberglass Reinforced Plastic (F.R.P.) flush door shutter in different plain and wood finish made with fire retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate all around, with suitable wooden blocks inside at required places for fixing of fittings and polyurethane foam (PUF)/Polystyrene foam to be used as filler material throughout the hollow panel, casted monolithically with testing parameters of F.R.P. laminate conforming to table - 3 of IS: 14856, complete as per direction of Engineer-in-charge.	sqm	10	4488.95	44889.50
8	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1: 4 (1 cement : 4 coarse sand) : 25 mm thick	sqm	2	1948.25	3896.50
9	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS: 15622 of approved make in colours such as white, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement: 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	sqm	8	1096.55	8772.40

Email.: principal@kmc.du.ac.in

दूरभाष:- 011-71219044



किरीडीमल कॉलेज

दिल्ली विश्वविद्यालय, दिल्ली-११०००७

KIRORI MAL COLLEGE

University of Delhi, Delhi-110007

NAAC Accredited A++ 3.54 CGPA, CYCLE 2 NIRF RANK 9

10	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. 11.41.2 Size of Tile 600x600 mm	sqm	2	1553.45	3106.90
11	Cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement. 12 mm cement plaster	sqm	10	449.55	4495.50
12	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gram/litre, of approved manufacturer and of required shade and colour all complete to achieve even shade and colour: New work (two or more coats) over and including water thinnable priming coat with cement primer having VOC content less than 50 gram/litre	sqm	200	185.65	37130.00
13	Finishing walls with Acrylic Smooth exterior paint of required shade: New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	sqm	5	160.6	803.00
14	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	sqm	150	155.9	23385.00
15	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sqm	250	156.05	39012.50
16	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	100	20.85	2085.00
17	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement: 4 fine sand)	sqm	20	547.4	10948.00
18	Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in- Charge.	each	1	134.1	134.10
19	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	cum	1	2434.25	2434.25
20	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	sqm	30	73.4	2202.00
21	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	5	54.65	273.25
22	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe 32 mm dia	each	10	119.55	1195.50
23	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 20 mm nominal dia Pipes	metre	5	335	1675.00
24	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 20 mm nominal dia Pipes	metre	10	537.6	5376.00
25	Providing and fixing uplasticsed PVC connection pipe with brass unions: 45cm length 15 mm nominal bore	each	10	97.75	977.50

Email.: principal@kmc.du.ac.in

दूरभाष:- 011-71219044



किरीडीमल कॉलेज

दिल्ली विश्वविद्यालय, दिल्ली-११०००७

KIRORI MAL COLLEGE

University of Delhi, Delhi-110007

NAAC Accredited A++ 3.54 CGPA, CYCLE 2 NIRF RANK 9

26	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931: 15 mm nominal bore	each	6	506.8	3040.80
27	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. 15 mm nominal bore	each	2	798.95	1597.90
28	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm nominal bore	each	8	574.3	4594.40
29	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately): 21.1.1 For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron)	kg	120	530.9	63708.00
30	P/F PVC pipe of approved quality, thickness, ISI marked as per IS:4985 (Finolex or equivalent) as per direction of Engineer-in-charge i/c making the joints leak proof a) PVC pipe 100/110 mm dia nominal bore.	mtr	10	1100	11000.00
31	P/F PVC pipe of approved quality, thickness, ISI marked as per IS:4985 (Finolex or equivalent) as per direction of Engineer-in-charge i/c making the joints leak proof a) PVC pipe 75/80 mm dia nominal bore.	mtr	5	800	4000.00
32	P/F PVC Nahni trap of approved quality, thickness, ISI marked as per IS:4985 (Finolex or equivalent) as per direction of Engineer-in-charge i/c making the joints leak proof 75 mm nominal bore	each	2	450	900.00
33	P/F PVC bend/ tee of approved quality, thickness, ISI marked as per IS:4985 (Finolex or equivalent) as per direction of Engineer-in-charge i/c making the joints leak proof				
a	75 mm nominal size	each	2	350	700.00
b	110 mm nominal size	each	2	450	900.00
34	P/F CP health faucet with flexible pipe complete	each	6	1200	7200.00
				Total	448034.27

Conditions:

1. The work should be completed in 60 days
2. 1% water/electricity charges will be recovered.
3. CPWD Specifications will be followed rigidly.
4. The bidder must visit the site of proposed work before submitting the bid.
5. Rates should be quoted both in words & figures.
6. Any other extra item or deviation other than the items of work order if required at site during the execution of work will be paid in accordance with the CPWD DSR-2023 or prevailing market rates as applicable with prior approval of competent authority.
7. Undersigned reserves the authority to reject any or all the quotations without assigning any reason thereof.


Principal

I/we hereby quote my/our rate as _____% above/below of the estimated rates.

Agency